

id 6446

جیک اپ ڈرلنگ رگ



3 جیک اپ ڈرلنگ رگ-سیلف ایبلونگ یونٹس-کنٹیلور کی قسم۔ برائے فروخت

| | |
|---|--------------------|
| 6446 | ج از کی شناخت |
| جیک اپ ڈرلنگ رگ | قسم |
| 2011 | سال کی تعمیر |
| \$2,500,000 | قیمت |
| 2022-10-11 | ج از شامل کی تاریخ |
| Horizon Offshore Services | ن شامل کیا |



ج از ک طول و عرض

| | |
|-----|--------------------------|
| 180 | مجموعی لمبائی (m), (LOA) |
| 25 | گ رائی, m |
| 14 | ج از کا مسود , m |

اضافی معلومات

خود سہ چلنے والا

ڈیکس

1

[میتے جلتے ج از دکھائیں](#)

اسی طرح ک ج از

[مماثلت کی درخواستوں کی خریداری](#)

درخواستیں

[ای میل بھیجیں](#)

ای میل



TECHNICAL DATA

GENERAL
 Rig Type: Three legs, self elevating unit, catwalk
 Design: Foster & Goddard L-750 Model 1 jacking
 Subier: Ardmore Corrosion SA, Buenos Aires
 Year Built: 1984, upgrade 2011
 Classification: ABS-A1 Self Elevating Drilling Unit
 Flag: Venezuela
 Accommodation: 86 + 1 hospital
 Max. Drill Depth: 25,000 ft / 7,620 m
 Max. Water Depth: 300 ft (91 m)
 Helideck: 70 ft diameter, rated for Sikorsk S-61 helicopter
 Operating Conditions: Wind speed 90 knots, wave height 25 ft
 Storm Conditions: Wind speed 100 knots, wave height 50 ft

TECHNICAL DIMENSIONS
 Length: 180 ft / 55 m
 Breadth: 176 ft / 53 m
 Depth: 25 ft / 7.6 m
 Crown Transit Draft: 14.5 ft / 4.4 m
 VDL - Operating: 2,070 cu ft / 58.7 m³
 VDL - Storm: 1,020 cu ft / 28.8 m³
 VDL - Crown Transit: 1,257 cu ft / 35.4 m³

CAPACITIES
 Liquid Mud: 1,021 bbls / 16,780 cu ft / 388 m³
 Drill Water: 3,572 bbls / 57,154 cu ft / 1,615 m³
 Potable Water: 1,300 bbls / 20,821 cu ft / 591 m³
 Fuel Oil: 2,500 bbls / 40,000 cu ft / 1,099 m³
 Bulk Mud: 4,000 cu ft / 113 m³
 Bulk Cement: 4,000 cu ft / 113 m³
 Bulk Material: 2,000 sacks

DRILLING EQUIPMENT
 Drivels: Siroco 180 ft x 30 ft x 30 ft, 1,040 kips
 shaft break tool
 Drawworks: Crown E-3000, 2,000 hp input;
 Drivage 70000 auxiliary drive
 Top Drive: Verso 700-S, 500 tons
 Iron Roughneck: Verso ST-90C
 Rotary: A 49 ft National Oilwell, independent drive
 Pipe Handling: Manual
 Mud Pump: 2 x National 12-HP 1800 spm
 1,800 HP each
 To Siroco 2 PPS-2000 Hoses - 2,000 HP



TECHNICAL DATA

GENERAL
 Rig Type: Four legs, self elevating unit,
 catwalk type
 Design: Sverdrup Offshore Company
 Subier: George Shipyard, Raritan
 Year Built: 1982, rebuilt in 2010
 Classification: Sertanoffshore Urigel
 Flag: Malta
 Accommodation: 86 + 2 hospital
 Helideck: 80 x 80 ft, rated for
 Puma SA 330 S-1
 80LL 212 - 417 helicopter
 Max. Drill Depth: 25,000 ft
 Max. Water Depth: 300 ft (91 m)
 Operating Conditions: Water 30 ft @ 12 kts
 Wind 50 knots
 Surface Current 2 knots

Storm Conditions: Water 30 ft @ 10 kts; Wind 80 knots
 Surface Current 2 knots

TECHNICAL DIMENSIONS
 Length: 172 ft / 52.42 m
 Breadth: 134.5 ft / 40.94 m
 Depth: 21 ft / 6.40 m
 Crown Transit Draft: 32 ft / 9.75 m
 VDL - Operating: 2,200 cu ft / 2,000 m³

CAPACITIES
 Liquid Mud: 1,000 bbls / 16,000 cu ft / 208 m³
 Drill Water: 3,300 bbls / 52,800 cu ft / 1,525 m³
 Potable Water: 1,212 bbls / 19,392 cu ft / 525 m³
 Fuel Oil: 1,640 bbls / 26,240 cu ft / 706 m³
 Bulk Mud: 4,000 cu ft / 113 m³
 Bulk Cement: 4,000 cu ft / 113 m³
 Bulk Material: 1,000 sacks



TECHNICAL DATA

Drill Shakers: 3 x S-250-1 type Brand Retro-45
 broken toolbit shaker
 Mud Cleaner: 1 x WSP 300 (replacement oilfield model)
 Desander: Brand 2 cones x 12 ft
 Desilter: Brand 18 cones x 8 ft
 BOP: 1 x 13-5/8 in Hydril 5 K Annular;
 1 x 13-5/8 in Cameron 1210 K Double;
 1 x 13-5/8 in Cameron 1210 K Single

Control System: Kongsberg 500 with 32 x 17 gal bottles &
 two remote control stations
 Choke & Kill: 1 x 4, 1/8 in 10K choke-in-line
 for ADS service
 1 x 2 - 1/2 in @ 5, 1 x 2 - 9/16 in @ 10K
 remote control chokes
 2 x 2 - 1/2 in @ 10 K, manual chokes

Third party

MACHINERY

Main Power: 2 x DMD 10-640-18 @ 2,200 HP each
 1 x DMD 10-640-18 @ 1,000 HP

Emergency Power: 1 x Caterpillar C-18, 587 HP, 400 V, AC

Power Distribution: 4 x Westinghouse Controls 1600 A, 2 x ICP
 ACCEL SERVENS

Deck Crane: 3 x Siggel Model 365,
 100 ft boom, 40 ft x 40 ft @ 50 ft

JACK-UP SPECIFICATIONS

Legs: Triangular 3 x 416 ft,
 Lattice below hull 276 ft

Leg Spacing: Longitudinal 115 ft,
 Transverse 130 ft

Spud Cams: 38 ft diameter x 20 ft height

Jacking System: National electric drive rack and pinion
 Container / Slot

Container 50 ft x 34 ft

MOORING EQUIPMENT

Winches: 4 x 75 tons, Siggel, 30W C75 single drum

Wire / Chain: 4 x 2,420 ft x 1 1/2 in wire

Anchors: 4 x 6,000 lb Shovel

